




Construction Start Date

Dates	8-24-20
Times	7am to 5pm

*Construction dates are subject to change, updates will be provided to the City of Scappoose.

Block closure from Miller Rd to Tyler St.

Trucks larger than 40' other than emergency and essential services to seek truck detour. All emergency and essential services are permitted to use construction zone for service in the construction zone.



Posted Speed	Spacing Between Signs			"Buffer" Space
	A	B	C	
20				50
25	100	100	100	75
30				100
35	350	350	350	125
40				150
45				180
50	500	500	500	210
55				250
60				285
65	700	700	700	325
70				365
Freeways:				
55				250
60				285
65	1000	1500	2640	325
70				365

Table 2-3: Taper Lengths and Device Quantities

Lane Width	10 Foot			11 Foot			12 Foot			Shoulder Tapers	
	MERGING	SHIFTING		MERGING	SHIFTING		MERGING	SHIFTING		L/J3	Cones
MPH	L	Cones	L	L	Cones	L	L	Cones	L	L	Cones
20	70	5	35	75	5	40	80	5	40	3	25
25	105	6	55	115	6	60	125	6	65	4	35
30	150	6	75	165	7	85	180	7	90	4	50
35	205	7	105	225	8	115	245	8	125	5	70
40	270	8	135	295	9	150	320	9	160	5	90
45	450	11	225	495	12	250	540	13	270	7	150
50	500	11	250	550	12	275	600	13	300	7	170
55	550	11	275	605	12	305	660	13	330	7	185
60	600	11	300	660	12	330	720	13	360	7	200
65	650	11	325	715	12	370	780	13	390	7	220
70	700	11	350	770	12	385	840	13	420	7	235

"L" for shoulder taper equals Shoulder Width x Speed.
Figures shown are for 10' shoulders.

Owner	Airpark		
Project Name	Scappoose Industrial Subdivision		
Prime Contractor	Tapani Inc		
Phone	360-687-1148	Sheet Number	4
Prepared By	Samantha Ortman (360)635-3323		
Date	8/9/19		