

**CONTRACTING AGENCY:**  
**PROJECT NAME:**

**CITY OF SCAPPOOSE**  
**DUTCH CANYON PRODUCTION WELL**

**ITB#:**  
**BID OPENING:**  
**BID OPENING WITNESSED BY:**  
**ARE BIDS LISTED IN THE ORDER O**

**BID RESULTS**  
**2023-01**  
**March 10, 2023 at 2:00 PM (PST)**  
**Huell Whitehaus, Susan Reeves**  
**Yes**

CONTRACTOR	OCCB#	SIGNED BID	FIRST TIER SUBCONTRACTOR'S FORM	10% BID GUARANTY	BID AMOUNT
Carpenter Drilling LLC	N/A	Yes	Yes	Yes	\$493,650.00
Jense Drilling Company	97276	Yes	Yes	Yes	\$337,700.00

**APPARENT RESPONSIVE LOW BID** Jensen Drilling Company

Bid Form Item No.	Items of Work and Materials	Approx. Quantity	Units	Carpenter Drilling		Jensen Drilling	
				Unit Price	Extended Price	Unit Price	Extended Price
1	Mobilization and Demobilization including all equipment and incidental items for installing a new production well, and site cleanup.	1	Lump Sum	\$95,000.00	\$95,000.00	\$27,000.00	\$27,000.00
2	Erosion Control.	1	Lump Sum	\$15,000.00	\$15,000.00	\$12,000.00	\$12,000.00
3	Turbidity Reduction and Water Management.	1	Lump Sum	\$10,000.00	\$10,000.00	\$17,000.00	\$17,000.00
4	Drill 20-inch borehole and complete surface seal.	80	Linear Feet	\$800.00	\$64,000.00	\$450.00	\$36,000.00
5	Drill minimum 16-inch diameter hole and furnish, install and remove temporary casing, as needed.	150	Linear Feet	\$650.00	\$97,500.00	\$350.00	\$52,500.00
6	Furnish, install and cut 16-inch diameter drive shoe	1	Lump Sum	\$18,500.00	\$18,500.00	\$1,500.00	\$1,500.00
7	Furnish and install 12-inch nominal 0.375 wall stainless steel casing (blank casing and sump).	22	Linear Feet	\$750.00	\$16,500.00	\$450.00	\$9,900.00
8	Furnish and install 12-inch pipe size stainless steel wire-wrap screen (provide manufacturer's specifications).	38	Linear Feet	\$750.00	\$28,500.00	\$550.00	\$20,900.00
9	Furnish and install filter pack assuming 60 feet. Cost includes casing pullback.	60	Linear Feet	\$450.00	\$27,000.00	\$350.00	\$21,000.00
10	Conduct plumbness and alignment testing.	1	Lump Sum	\$7,500.00	\$7,500.00	\$7,500.00	\$7,500.00
11	Conduct well development – impulse generation and dual-isolation surging and pumping.	40	Hours	\$1,050.00	\$42,000.00	\$750.00	\$30,000.00
12	Conduct well development – Pumping with test pump.	8	Hours	\$850.00	\$6,800.00	\$750.00	\$6,000.00
13	Furnish, install and remove power for pump, test pump, temporary discharge line, and valves and appurtenances.	1	Lump Sum	\$12,450.00	\$12,450.00	\$55,000.00	\$55,000.00
14	Run step-rate test and constant-rate test.	30	Hours	\$850.00	\$25,500.00	\$750.00	\$22,500.00
15	Perform video inspection of well casing and screen.	1	Lump Sum	\$2,500.00	\$2,500.00	\$5,000.00	\$5,000.00
16	Perform well disinfection.	1	Lump Sum	\$4,500.00	\$4,500.00	\$5,400.00	\$5,400.00
17	Perform production well surface completion.	1	Lump Sum	\$10,000.00	\$10,000.00	\$4,500.00	\$4,500.00
18	Standby time.	8	Hours	\$650.00	\$5,200.00	\$250.00	\$2,000.00
19	Preauthorized hourly work.	8	Hours	\$650.00	\$5,200.00	\$250.00	\$2,000.00
<b>TOTAL BASE BID PRICE – ITEM NO.'S 1 THROUGH 20:</b>					<b>\$493,650.00</b>		<b>\$337,700.00</b>